

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>X</u> , R. <u>31</u> E. <u>X</u> W.	<u>J3</u>
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	T. <u>45</u> N. <u>X</u> , R. <u>31</u> E. <u>X</u> W.	<u>16, 1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ S. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 12, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 16:**

Not set on original survey nor subsequently, apparently.

**Corner 1:**

Not set on original survey nor subsequently, apparently.

**Corner J3:**

Original monument and accessories not found. Found 3" aspen post N78°E 21.5 ft. by Mead Corp. cruisers.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 16:**

Established on line midway between corners E & W.

**Corner 1:**

Established on line midway between corners E & W.

**Corner J3:**

Reestablished on line between corners E & W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 16:** Set 1" I.D. x 36" iron pipe with 3-1/2" aluminum cap.

9" Spruce S52°E 98.8 ft., 1/16S, BT

7" Spruce S16°W 77.5 ft., 1/16S, BT

**Corner 1:** Set 1" I.D. x 36" iron pipe with 3-1/2" aluminum cap.

7" Maple N5°E 13.1 ft., 1/16S, BT

5" Maple S9°E 38.5 ft., 1/16S, BT

**Corner J3:** Set 1" I.D. by 36" iron pipe with 3-1/2" aluminum cap.

5" W. Pine N 8°W 49.4 ft., 1/4S, NBT

5" Maple S68°W 26.6 ft., 1/4S, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson DATE \_\_\_\_\_

Carl R. Johnson

APPROVED AND SIGNED BY Keith L. Sackett DATE 5/30/80

MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

