

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(IRON COUNTY)

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>31</u> W. <u>X</u> S. <u>X</u> R. _____	K-6
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>45</u> N. <u>31</u> W. <u>X</u> S. <u>X</u> R. _____	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 31, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K-6: Original monument and accessories not found.

Corner 14: Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K-6: Restored on line between Sec. Cor. 40.000 chains south and Sec. Cor. 41.000 chains north. There appears to have been a 1.00 chain blunder in the original survey of this section line, somewhere between the south bank of Michigan River and section corner north of it. Distance between river and north edge of lake to south of it agrees perfectly with record, therefore, blunder could not have occurred there; the section line between Sec. 11 & 12 also agrees nearly perfectly with the record so the blunder is not likely to have been there either; which leads to the conclusion I have stated.

Corner 14: Established on line between corners 20.000 ch. north and 20.000 ch. south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner K-6: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
8" Spruce S37°E 30.8 ft., 1/4S, NBT
7" Spruce S54°W 32.4 ft., 1/4S, NBT**

**Corner 14: Set 1" I.D. x 32" iron pipe with 4" aluminum cap.
11" Maple S14°E 2.5 ft., 1/16S, BT
8" Maple N86°W 38.5 ft., 1/16S, BT**

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl P. Johnson DATE 9-3-80

APPROVED AND SIGNED BY Keith L. Sackett DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

