

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>H12</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S <u>34</u> T <u>45N</u> R <u>31W</u>	<u>8</u>	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Aug 29 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		●●		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (H12) Center of Section 34. Not established in the original survey.
 (8-Sec. 34) West 1/16 corner, Section 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
 (8-Sec. 34) Established the corner midway and on a straight line between monumented Quarter corner and Center of Section 1327.15' West and East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:	(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
11" Spruce S65E 20.8' "C1/4 BT"	15" Sugar N64E 10.6' "1/16S BT"
6" Spruce S25E 19.1' do	20" Sugar S19E 18.5' do
10" Spruce S45W 11.7' do	8" Sugar S29W 21.5' do
9" Spruce N85W 27.9' do	9" Sugar N75W 17.6' do
Set a sq'd spruce post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/9/02