

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>G11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>45N</u> R <u>31W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Aug 28 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(G11) Corner common to Sections 27-28-33-34. 1849: Established by John Burt, D.S.: North between Secs. 33 & 34...80.00 Set Sugar post cor. of Secs. 27,28,33 & 34. Lynn 16 S09E 16, Lynn 14 N51W 16. Found no subsequent record.  
 (1-Sec. 34) West 1/16 corner between Sections 27 and 34. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G11) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record from found Quarter corners G6 198.9503 ch. north, G12 39.7908 ch. south, B11 199.9383 ch. west, and Section corner I11 79.7878 ch. east. Found no original evidence at the intervening Quarter and Section corners. Found a squared 4"x4" post, 4' long, approx. 25' Westerly from the reestablished position - apparently a forester's approximation of the corner. Removed the post and placed it adjacent to the monument.  
 (1-Sec. 34) Established the corner midway and on a line of mean true bearing between Section and 1/4 corners 1316.50' West and East.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:	(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
11" Sugar N72E 21.8'      "S27 NBT"	18" Sugar N81E 70.2'      "1/16S BT"
11" Sugar S47E 11.1'      "S34 NBT"	8" W.Spruce S64E 24.7'      do
9" Sugar S22W 10.1'      "S33 NBT"	5" Sugar S86W 64.8'      do
7" Sugar N47W 34.4'      "S28 NBT"	3" Tamarack N20W 16.3'      do
Bearings are magnetic. Distances are to notch in lower blaze.	Placed sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/9/02