

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>G12</u>	
	T <u>45N</u> R <u>31W</u>	<u>H11</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____	_____	_____
	S _____ T _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____	_____
	S _____ T _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

H11 Aug 28 2002  
 G12 Aug 07 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11								●					
12	31		32		33		●	34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(G12) Quarter corner common to Sections 33-34. 1849: Established by John Burt, D.S.: North between 33 and 34...40.00 Set Y. Birch qr Sect. post. Sugar 14 S81E 16, Sugar 16 N62W 21. ...80.00 Set Sugar post cor. of Sec. 27,28,33, & 34. Found no subsequent record.  
 (H11) Quarter corner common to Sections 27-34. 1849: Record of John Burt, D.S. states: West corrected between Sec. 27 & 34...39.00 Pond, 39.95 Qr. Section corner in pond, 42.00 Over pond ...79.90 Section corner. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G12) The original post was not recovered. Remonumented the corner at record bearing and distance from the probable remains of the 1849 OBTs: A dead, hollow, 28" DBH Sugar with healed scars and location poster attached, S81E 16 links, and a stump hole N62W 21 links. Measured bearings and distances to adjacent Section corners: S 12'00" E 2624.05' to a 1968 MDNR monument of record, and N 20'22" E 2626.19' to a MDNR monument at a reestablished position (True bearings).  
 (H11) Reestablished the corner midway and on a line of mean true bearing between Section corners 2633.01' east and west. The position falls in a murky pond and cannot be monumented. Monumented a Witness Corner, on the Section Line S 89 deg. 49'01" E (True brg.), 75.00' from the corner, the accessories for which Witness Corner are described below. Placed a squared cedar post approximately 5' south of the 1/4 corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G12) Set 1"x32"ID I.pipe with 4" alum. MDNR cap. Blazed and scribed: 5" Sugar N66E 12.1' "1/4S NBT" 14" Sugar S15E 21.4' do 11" Sugar S68W 17.0' do 8" Sugar N77W 11.1' do Squared a 5" Sugar S79E 3.7' to center. Bearings are magnetic. Distances are to notch in lower blaze.	(H11) Set a 1"IDx32" I.pipe with 4" alum. MDNR cap as a WITNESS CORNER, on the Section line 75.00' easterly. Blazed and scribed: 8" W. Pine S71W 13.0' "WC BT" 6" Tamarack N68W 39.4' do 9" Cedar N54W 28.5' do 13" Tamarack N39W 9.2' do Placed a sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
---	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 9/9/02