

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>C1</u>
	T <u>45N</u> R <u>31W</u>	<u>A6</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 06 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Corner common to Sections 5-6 T45N-R31W and 31-32 T46N-R31W. Remonumented in 1993 by the undersigned at the position of the remains of an old cedar post, a perpetuation of the original corner. Set 1"IDx36" I.pipe with 4" alum. MDNR cap. 25" Cherry N12E 4.9', 12" Maple N77W 29.7', 5" Maple S18W 16.4', 5" Sugar S52E 11.7'.
 (A6) Quarter corner common to Section 18 T45N-R31W and Section 13 T45N-R32W. Reestablished in 1970 by A.O.Enger RLS on line between Section corners 40.016 ch. to north and south. Set 1"IDx36" Iron pipe with 4" aluminum cap. Sugar Maple 8 N15W 19.1', Sugar Maple 9 S26W 18.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) Recovered the 1993 monument in good condition and at record bearing and distance from the 1993 accessories, which are now dead. Left the monument in place and made new witnesses.
 (A6) Recovered the 1970 monument in good condition and at record bearing and distance from the 1970 witness trees, both in good condition with overgrown blazes. The monument is located less than 1.0' from the position of record and is accepted as a careful and faithful reestablishment of the position of the original corner. Made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" Sugar S76E 17.4' mrkd "S5 NBT" 14" Sugar S06E 43.5' do 4" Sugar S36W 32.8' mrkd "S6 NBT" 6" Sugar S67W 31.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(A6) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 10" Sugar N11W 19.5' * 13" Sugar S31W 19.0' * 8" Sugar S46E 11.7' mrkd "1/4S NBT" 11" Sugar S72W 25.8' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	--

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/12/05

For the Michigan Department of Natural Resources, Office of Land and Facilities