

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45NR</u> <u>31W</u>	<u>J7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>45NR</u> <u>31W</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

J7 Apr 12 2006
 10 Apr 11 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J7) Quarter corner common to Sections 14 and 23. 1980 - Reestablished by K.L.Sackett RLS by proportionate measurement to the original record between Section corners. Mr. Sackett set a 1"IDx32" I.pipe with 4" aluminum cap and made the following witnesses: 10" Spruce N78E 34.4', 5" Spruce N29W 30.4'.
 (10-Sec. 23) South 1/16 corner between Sections 22 and 23. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J7) Recovered the 1980 monument in good condition and at substantial record bearing and distance from one 1980 witness tree. The 5" Spruce noted in the record is actually a W.Pine, with overgrown blazes. The record distance to this tree appears to be a slope distance. The 1980 NBT 10" Spruce was not recovered - likely destroyed by logging and roadbuilding. The position of the monument is only 0.44' east of the proportionate position of record and I consequently accept the monument as a careful and faithful reestablishment of the position of the original corner.
 (10-Sec. 23) Established the corner midway and on a straight line between Section corner 1309.41' South and Quarter corner 1309.41' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J7) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: W.Pine N23W 30.0' old blazes * 8" Spruce N15E 21.8' mrkd "1/4S NBT" 5" Poplar S01W 50.4' do 7" Spruce S57W 24.1' do Exist. sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1908 NBT.	(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Sugar N36E 14.9' mrkd "1/16S BT" 9" Sugar S72E 7.2' do 6" Sugar S44W 6.4' do 6" Sugar N49W 12.6' do Set Sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/1/06

For the Michigan Department of Natural Resources, Office of Land and Facilities