

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>45NR</u> <u>31W</u>	<u>J8</u>
	T <u>    </u> <u>    </u>	<u>    </u>
	T <u>    </u> <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> <u>    </u>	<u>    </u>
	S <u>23</u> T <u>45NR</u> <u>31W</u>	<u>9</u>
	S <u>    </u> T <u>    </u> <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

9 Apr 10 2006  
 J8 Apr 12 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (J8) Center of Section 23. Not established in the original survey. Found no subsequent record.
- (9-Sec. 23) East 1/16 corner, Section 23. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J8) Established the corner at the intersection of 1/4 lines. The N-S 1/4 line is a straight line between 1/4 corners of record. The E-W 1/4 line is at mean bearing of the North and South lines of the Section, passing through the West 1/4 corner.
- (9-Sec. 23) Established the corner on the E-W 1/4 line of Section 23, 1317.67' East of the Center of Section 23. The distance is the mean of the north line of the NW1/4 of the NE1/4 of Section 23 and the south line of the SW1/4 of the SE1/4 of Section 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (J8) Set 1/2"x9" rebar in 3/4"x5" hole drilled into rock and encased in a 1"IDx8" I.pipe with 4" alum. cap, the whole made firm with concrete and a rock mound 3' dia.x1.2' tall. Set measuring nails in: | (9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:              |
| 7" dbl Maple N68W 60.5' mrkd "C1/4 BT"  | 7" Spruce S66W 22.3' mrkd "1/16S BT"   |
| 5" Spruce S74E 51.2' do   | 5" Spruce N58W 54.0' do  |
| 5" dbl Maple N80E 87.4' do  | 4" Maple N61E 50.3' do   |
| 10" Maple (no bearing rec.) 68.5' do  | 8" Sugar S57E 18.0' do   |
| Bearings are magnetic. Distances are to nail with tag.  | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/1/06

For the Michigan Department of Natural Resources, Office of Land and Facilities