

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>K7</u>
	T <u>45N</u> R <u>31W</u>	<u>MC North of K9</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	MC Apr 11 2006	
	K7 Apr 10 2006	

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7										●		
8	19	20	21	22	23	24				●		
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K7) Corner common to Sections 13-14-23-24. 1980 - Reestablished and monumented by A.O.Enger RLS. Mr. Enger placed a 1"IDx36" iron pipe with a 3-3/4" aluminum cap and made witnesses: W.Spruce 18 N10E 48.1', B.Spruce 6 N86W 22.9'.
 (MC North of K9) Meander corner on the east line of Section 23 at the south shore of Hickman Lake. 1980 - Reestablished by K.L.Sackett RLS at record distance (31.15 chains) north of Section corner K9 and on the Section line. Mr. Sackett Set a 1"IDx32" Iron pipe with 4" aluminum cap and made the following witnesses: 3" Tamarack N85W 28.9', 3" Tamarack S08E 14.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Recovered the 1980 monument in good condition, with wooden post adjacent, and at record bearing and distance from the 1980 witnesses, now both dead and down. One of the 1980 NBTs has been cut by loggers, the other is a windthrow. Checked the distance south to K9 and found it to be 78.4046 chains, agreeable with Mr. Enger's record of 78.4245 chains. Left the monument in place and made new witnesses as described below.
 (MC) Recovered the 1980 monument, disturbed by ice action, under 8" of water, and leaning heavily to the SW. Re-set the 1980 monument at record bearing and distance from the 1980 NBTs, both found in good condition. Made the monument as firm as possible with four 2.5" dia.x7 ft. long tamarack hubs and misc. smaller pieces of tamarack. Found distance south to K9 of record to be 2054.88' (31.135 chains).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Fd. 1"ID iron pipe with alum. MDNR cap. Set measuring nails in:	(MC) Reset 1980 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
19" Spruce N15W 59.8' mrkd "S14 NBT"	5" Tamarack N84W 29.0' old blazes *
6" Spruce S79E 69.1' "S24 NBT"	4" Tamarack S04E 14.4' do *
8" Poplar S15E 14.8' "S24 NBT"	4" Tamarack S07W 19.3' mrkd "MC NBT"
4" Spruce N80W 12.6' "S14 NBT"	5" Tamarack S45W 42.8' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1980 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/1/06

For the Michigan Department of Natural Resources, Office of Land and Facilities