

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S 18 T 45N R 31W	4
	S 18 T 45N R 31W	8
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 10 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6	●	18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (4-Sec. 18) Northwest 1/16 corner, Section 18. Not established in the original survey.
- (8-Sec. 18) West 1/16 corner, Section 18. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (4-Sec. 18) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
- (8-Sec. 18) Established the corner 20.00 chains, proportionate to the original plat, West of the Center of Section and on a straight line between the Center of Section 1317.88' East and Quarter corner 1310.63' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (4) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap in a 2.5' dia. x 1.5' high
mound of rock. Set measuring nails in: | (8) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: |
| 12" Sugar N30W 12.5' mrkd "1/16S BT" | 8" Sugar N31E 21.0' mrkd "1/16S BT" |
| 6" Sugar N85E 9.5' do | 10" Sugar S66E 4.8' do |
| 9" Sugar S13E 19.3' do | 5" Sugar S23W 13.4' do |
| 5" Sugar S88W 23.4' do | 7" Sugar N50W 4.7' do |
| Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/12/05