

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S 18 T 45N R 31W	11
	S 17 T 45N R 31W	12
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

12 Oct 11 2005
 11 Oct 10 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 18) Southwest 1/16 corner, Section 18. Not established in the original survey.
 (12-Sec. 17) South 1/16 corner, Section 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 18) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.
 (12-Sec. 17) Established the corner midway and on a straight line between Center of Section 17 (unmonumented) 1325.00' North and Quarter corner 1325.00' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Sugar N21W 25.4' mrkd "1/16S BT" 6" Sugar N76E 12.9' do 17" Sugar S02E 9.0' do 7" Sugar S89W 27.0' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Spruce N12W 10.4' mrkd "1/16S BT" 6" B.Spruce S46W 24.0' do 11" Spruce S87W 27.5' do 12" Spruce N66W 12.3' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 10/12/05

For the Michigan Department of Natural Resources, Office of Land and Facilities