

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located in:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S 23 T 45NR 31W	14
	S 23 T 45NR 31W	8
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

8 Apr 13 2006  
 14 Apr 12 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 23) South 1/16 corner between Sections 23 and 24. 1980 - Established by K.L.Sackett RLS on line between Section corner 20.00 chains south and Meander Corner 11.15 chains north. Set 1"IDx32" I.pipe with 4" aluminum cap. 6" Aspen S76E 14.4', 8" Aspen N44W 54.0'.  
 (8-Sec. 23) West 1/16 corner, Sec. 23. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14) Recovered the 1980 monument in good condition, 0.1' below ground surface, both BTs now gone. Measured distances south 1319.60' to Section corner and north 735.27' to MC, this monument being 0.25' West of a straight line between them. Accepted the monument as a careful and faithful establishment of the position of the corner.  
 (8-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1323.02' west and Center of Section 1323.02' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:	(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
10" Poplar S16E 27.1' mrkd "1/16S BT"	3" Maple N19E 34.7' mrkd "1/16S BT"
4" Poplar N79E 30.8' do	2" Maple N57E 24.9' do
7" Spruce N20E 112.9' do	4" Cherry S59W 18.3' do
7" Balsam N52W 99.2' do	4" Aspen N44W 6.4' do
Existing cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	Set sq'd cedar 4"x4" post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/1/06

For the Michigan Department of Natural Resources, Office of Land and Facilities