

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>E1</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>4</u> T <u>45N</u> R <u>31W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 05/12/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E1) Corner common to Sections 4-5 T45N-R31W and Sections 32-33 T46N-R31W. 1968 - A.O.Enger RLS remonumented the corner at the location of a 2" squared picket found at record bearing and distance from two W.Pine stumps presumed to be the original BTs. Set 1"IDx36" I.pipe with 4" aluminum cap. Sugar Maple 10" N29W 21.5 links, Red Maple 6" S20W 32.5 links, Sugar Maple 8" N89E 18.5 links.

(3-Sec. 4) North 1/16 corner between Sections 4 and 5. Not established in the original survey. The original plat of this township shows dimensions 20.00 chains south to 1/4 corner and 20.13 chains north to Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E1) Found the 1968 monument in good condition and at record bearing and distance from the Sugar Maple NW and Red Maple SW NBTs, both in good condition with overgrown blazes. No evidence of the Sugar Maple NBT N89E was observed above the snow. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(3-Sec. 4) Established the corner on the Section line between Quarter corner 1322.14' south and Section corner 1330.74' north, being proportionate to the dimensions given on the original plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E1) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 15" Sugar N25W 13.8' 1968 NBT
 10" Maple S21W 21.9' do
 8" Sugar N72E 24.9' mrkd "S33 NBT"
 8" Sugar S27E 23.4' "S4 NBT"
 Sq'd cedar post adjacent. Bearings magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Sugar N25E 18.3' mrkd "1/16S BT"
 15" W.Spruce N75E 29.7' do
 7" Sugar S05E 11.1' do
 6" Sugar N16W 9.0' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/26/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16496
16495