

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>45N</u> R <u>31W</u>	_____ 16
	S <u>4</u> T <u>45N</u> R <u>31W</u>	_____ 13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2			1
3												
4	7	8			9		10		11			12
5												
6	18	17			16		15		14			13
7												
8	19	20			21		22		23			24
9												
10	30	29			28		27		26			25
11												
12	31	32			33		34		35			36
13												

I, Stephan J. Szyszkoski, in a field survey on 16 05/13/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(16-Sec. 4) East 1/16 corner between Sections 4 and 9. 1971 - Established by A.O.Enger RLS on line between section corner 19.917 ch. east and 1/4 corner 19.917 ch. west. Set 1"IDx36" I.pipe with 4" aluminum cap. R.Maple twin 5" N51 1/2E 32.7', R.Maple 5" S76E 35.9'.

(13-Sec. 4) Southeast 1/16 corner, Section 4. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(16-Sec. 4) Found the 1971 monument in good condition and at record bearing and distance from the 1971 witnesses. The R.Maple twin NE is in good condition with overgrown blazes. The R.Maple SE is dead and down. Checked the position of the monument with respect to section corner 1311.85' east and quarter corner 1311.91' west and found it to be substantially in accord with the record. Accepted the monument as a careful and faithful establishment of the position of the corner.

(13-Sec. 4) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(16) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" twin Maple N56E 32.5' 1971 BT  
 10" Maple S47E 54.4' mrkd "1/16 S BT"  
 2" Poplar N85W 53.4' " X X "  
 2" Poplar N06W 52.2' do  
 Sq'd cedar post adjacent. Bearings magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" twin W.Birch S03E 17.0' mrkd "1/16S BT"  
 5" Balsam S84W 14.6' do  
 2" W.Spruce S29W 10.3' mrkd " X X "  
 2" W.Spruce N21W 30.7' do  
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/26/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division