

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 31W	E2
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 4 T 45N R 31W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 12 06/23/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E2) Quarter corner common to Sections 4 and 5. 1970 - Reestablished by A.O.Enger RLS proportionately on line between an original section corner 40.06 ch. south and an original section corner 40.19 ch. north. Set 1"IDx36" iron pipe with 4" aluminum cap. Spruce 6" S79E 19.7', Spruce 6" N49W 10.3'.

(12-Sec. 4) South 1/16 corner Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E2) Found the 1970 monument in good condition and at record bearing and distance from the Spruce NBT SE, in good condition with scribing visible. Found no evidence of the Spruce NW NBT above the snow. Checked the position of the monument with respect to section corners found 2644.16' south and 2652.88' north and found it to be substantially in accord with the record. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(12-Sec. 4) Established the corner midway and on a straight line between Quarter corner 1320.28' south and the intersection of 1/4 lines of Section 4 1320.28' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E2) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Spruce S75E 20.0' 1970 NBT
 10" W.Spruce N76E 6.2' mrkd "1/4S NBT"
 8" Maple S40W 14.3' do
 10" Maple S75W 17.4' do
 Sq'd cedar post adjacent. Bearings magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 18" W.Pine S63E 25.7' mrkd "1/16S BT"
 10" W.Pine S14E 21.8' do
 4" W.Spruce N80W 26.0' do
 15" W.Pine N62W 19.8' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/26/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division