

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|---|---------------|
| <u>Iron</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T _____ R _____ T 45N R 31W | G3 |
| 2. Property Controlling in Section | S 4 T 45N R 31W S _____ T _____ R _____ S _____ T _____ R _____ | 14 |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | 8 | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 06/23/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 4) South 1/16 corner between Sections 3 and 4. 1970 - Established by A.O.Enger RLS on line between section corner 19.988 ch. south and 1/4 corner 19.988 ch. north. Set 1"IDx36" iron pipe with 4" aluminum cap. Tamarack 14" S55E 18.3'. No other trees or suitable objects near.

(G3) Corner common to Sections 3-4-9-10. 1970 - Reestablished by A.O.Enger RLS by double proportionate measurement from corners 1 mile N., 1.5 miles S., 3 miles E., and 1 mile W. Set 1"IDx36" I.pipe with 4" aluminum cap. B.Spruce 10" N09E 17.0', B.Spruce 12" S64E 26.2', B.Spruce 10" S40W 65.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 4) Found the 1970 monument in good condition, squared cedar post adjacent, at record bearing and distance from the Tamarack BT witness, now a dead stub with scribing visible. Checked the position of the monument with respect to section corner 1318.80' south and quarter corner 1318.57' north and found it to be substantially in accord with the record. Accepted the monument as a careful and faithful establishment of the position of the corner.

(G3) Found the 1970 monument in good condition and at record bearing and distance from the 1970 witnesses, now all dead and down. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Spruce S20E 66.5' mrkd "1/16S BT"
 2" Tamarack N89E 37.5' mrkd " X X "
 2" Tamarack S64E 26.3' do
 2" Tamarack N44W 40.0' do
 Bearings are magnetic.

(G3) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Spruce S89E 7.5' mrkd "S10 NBT"
 11" W.Birch S24W 7.4' "S9 NBT"
 4" Spruce S77W 14.8' "S9 NBT"
 9" Spruce N14W 17.4' "S4 NBT"
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/26/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division