

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>31W</u>	<u>12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>2</u> T <u>45N</u> R <u>31W</u>	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 2 07/20/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I2) Quarter corner common to Sections 2 and 3. 1849 - Established by John Burt Deputy Surveyor on the Section line between Section corners 40.00 chains south and 40.89 chains north. 1970 - Reestablished by A.O.Enger RLS on the Section line between Section corners 40.083 chains south and 40.975 chains north (proportionate to the 1849 measure). Set 1"IDx36" I.pipe with 4" aluminum cap. W.Pine 20" S10E 33.7', W.Spruce 7" N35E 30.9'.

(12-Sec. 2) South 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I2) Found the 1970 monument disturbed and out of position. The 1970 witnesses were not recovered. Reestablished the corner on the Section line between Section corners 2643.84' south and 2702.67' north (proportionate to the 1849 and 1970 records).

(12-Sec. 2) Established the corner midway and on a straight line between Quarter corner 1320.53' south and Center of Section 1320.53' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" Balsam N72E 23.75' mrkd "1/4S NBT"
 25" W.Pine S02E 32.8' do
 5" Maple S57W 38.05' do
 15" W.Pine N40W 36.7' do
 Sq'd cedar post adjacent.
 Bearings are magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 3" B.Spruce N09W 5.25' mrkd "1/16S BT"
 3" B.Spruce N70E 19.75' do
 3" B.Spruce S55E 13.55' do
 3" B.Spruce S45W 5.5' do
 Sq'd cedar post adjacent.
 Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3	●	2			1
3										●			
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/17/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities