

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S <u>2</u> T <u>45N</u> R <u>31W</u>		<u>5</u>
	S <u>2</u> T <u>45N</u> R <u>31W</u>		<u>J2</u>
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1									●			
2	6		5		4		3		●			1
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on J2 07/21/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(5-Sec. 2) North 1/16 corner, Section 2. Not established in the original survey.

(J2) Center of Section 2. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(5-Sec. 2) Established the corner on a straight line between Center of Section 1321.56' south and Quarter corner 1392.92' north, being proportionately 20.00 chains and 21.08 chains, respectively, as derived from the original plat of this township.

(J2) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" twin Sugar N62E 9.0' mrkd "1/16S BT"  
 4" Sugar S58E 31.45' do  
 5" Poplar S18W 2.0' do  
 3" Balsam N61W 3.2' do  
 Sq'd cedar post adjacent.  
 Bearings are magnetic.

(J2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" Cherry N17W 27.6' mrkd "C1/4 BT"  
 8" Balsam S67E 5.9' do  
 6" Spruce South 17.2' do  
 7" Spruce S53W 29.3' do  
 Sq'd Cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

