

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W	I1
	T 45N R 31W	K2
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on I1 07/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I1) Corner common to Sections 2-3 T45N-R31W and Sections 34-35 T46N-R31W. 1969 - Reestablished by A.O.Enger RLS on line between Section corners 79.83 chains east and west. Set 1"IDx36" I.pipe with 4" alum. cap. Sugar 5" N47W 6 links, Sugar 4" S36 1/2E 16 links, Sugar 7" N59E 57.5 links.

(K2) Quarter corner common to Sections 1 and 2. 1980 - Reestablished by K.L.Sackett RLS on line between Section corners 40.000 chains south and 41.270 chains north (at the original record position). Set 1"IDx36" I.pipe with 4" alum. cap. 7" Tamarack S21E 15.3', 7" Tamarack N38W 11.6', 16" W.Pine S51W 28.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I1) Found the 1969 monument in good condition and at record bearing and distance from the 1969 witnesses. The Sugar NBTs NW and SE are in good condition, the Sugar NBT NE is dead and down. Accepted the corner position and used it to reestablished Quarter corner I2 this date.

(K2) Found the 1980 monument in good condition and at record bearing and distance from the 1980 witness trees. The two 7" Tamaracks, now 9", are in good condition with overgrown blazes. The W.Pine SW is standing dead. Found the monument to be at the record position, 2638.23' north of Section corner K3 and 2722.38' south of Section corner K1. Accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I1) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 7" twin Sugar N35W 4.0' old blazes 1969 NBT
 6" triple Sugar S25E 10.75' do do
 10" Sugar S80W 18.9' mrkd "S3 NBT"
 4" Balsam S69E 10.15' "S2 NBT"
 Bearings are magnetic.

(K2) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Tamarack N36W 11.85' old blazes 1980 NBT
 9" Tamarack S18E 15.5' do do
 6" Tamarack N56E 2.8' mrkd "1/4S NBT"
 6" B.Spruce S80W 15.0' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/17/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities