

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 31W	J3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 07/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner common to Sections 2-11. 1980 - Reestablished by K.L.Sackett RLS on line between corners East and West. Set 1"IDx36" I.pipe with 3 1/2" alum. cap. 5" W.Pine N08W 49.4', 5" Maple S68W 26.6'. The original measure of this mile was 79.81 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) Found the 1980 monument in good condition and at record bearing and distance from the remaining NBT SW, a Sugar Maple, now 9", with old overgrown blazes. The W.Pine NBT was not recovered. Found the position of the monument to be substantially at record position, on line between Section corners 2612.83' west and 2611.96' east. Accepted same as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Fd. 1"ID I.pipe with 3.5" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 9" Sugar S70W 27.0' old blazes 1980 NBT
 10" Spruce S16W 31.85' mrkd "1/4S NBT"
 5" Spruce N10W 9.0' do
 7" Poplar S89W 22.95' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities