

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 32 K. W.	D3 ✓
2. PROPERTY CONTROLLING IN SECTION	T. 45 N. R. 32 K. W.	2 ✓
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law.

A. Description of original monument and accessories and/or subsequent restoration:

Corner D3: Original monument and accessories not found. Found old post and location poster. Post apparently used for subdivision on Deer Lake.

Corner 2: Not set on original survey. Found T Iron in concrete.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D3: Restored at old post.

Corner 2: Restored at T iron. This corner set at SW corner of Deer Lake Plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D3: Set 1" I.D. by 32" Iron pipe with 4" Alum. cap.
 10" Spruce S05W 22.2 ft. 1/4S, NBT
 4" Balsam N64W 9.6 ft. 1/4S, NBT
 12" Balsam S75E 31.7 ft. 1/4S, NBT

Corner 2: T iron in concrete.
 5" Balsam N08E 71.1 ft. 1/16S, BT
 3" Balsam N50E 34.2 ft. 1/16S, BT


SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-1-84

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006