

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES


LAND CORNER RECORD

Iron COUNTY
T 45 N R 32 W

DESCRIPTION OF CORNER Section corner 15, 16, 21 and 22
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap placed 2.5 feet east of original corner tree. Cap stamped "Corner is 2½ feet West."

DATE MONUMENT PLACED AND WITNESSED March 17, 1970

WITNESSES TO ~~CORNER~~ Iron Pipe: Sugar Maple 20 S28°E (magnetic) 14.3 feet "S22, NBT"



Sugar Maple 14 S60°W (magnetic) 30.8 feet "S21, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Subsequent accessories by unknown surveyors:

Sugar maple 10 N35°W 46½ links "S16, BT"

Sugar maple 24 S37°W 28 links (scribed, unreadable)

Identified remnant stump of 1854 corner tree. Tree had split, exposing old squared section at center of tree. Much evidence of continuous use of this location for the corner. Deep snow may have obscured current evidence of any original BT's. Sugar Maple 24 noted above is very old, possibly a non-recorded "section tree" made by the Examining Deputy Surveyor.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE August 24, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68