

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 44-45 N R 32 W

DESCRIPTION OF CORNER Section Corner 1, 2, 35, and 36

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 6, 1968

WITNESSES TO CORNER..... Red Maple 8 S6°W 39½ lks. "S2 NBT"



Sugar Maple 6 S50°E 18 lks. "S1 NBT"

Red Maple 7 N75°E 27½ lks. "S36 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner set from a probable original BT, W. Pine 50 S30W 18, found by measuring eastward along a transit line from a reputed original corner 159.98 chains west. Record distance is shown as 160.00 chains. Pine stump is badly rotted and has no marks, but shows agreement with original in species and size.

Corner position lies 3.70 chains east of a 5 ft. high granite ledge mentioned in original field notes as being 3.75 chains west of the corner. If the corner were as little as one chain north or south of this position it would not agree with the call to the ledge.

This corner position lies very close to the extension of a straight line between original corners lying 2 and 3 miles west. No positive evidence of original corner; but the corner position is considered to be duly supported by collateral evidence.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/14/69  
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68