


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

_____ Iron _____ COUNTY
T 45-46N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 32
CORNER MONUMENT 1" I.D. x 3/6" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 12, 1969
WITNESSES TO CORNER..... Black spruce 4 S11 1/2°W 21 links "1/4S NBT"



White spruce 11 N45 1/2°W 80 1/2 links "1/4S NBT"

Bearings are magnetic

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of a 1 1/2"x25" solid round iron bar, a 1" I.D. x 3/6" jointed iron pipe with 2" brass cap (by Northern Paper Mills), and an old squared wood post. Also found rotted remains of an elder wood post in the ground. These monuments appear to have been placed from an original BT described as a W. Pine 24 N40E 54 links. This tree evidently stood in what is now a gravel road and at the time of road construction the BT stump was removed to its present position bearing S12 1/2°W 41 links from the corner monuments, with slabs of the original witness face and scribe marks "1/4" plain.

Corner is on south edge of an east and west road.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

2/26/70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68