

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

1407

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 32 W.	E 3
2. PROPERTY CONTROLLING IN SECTION	T. 45 N. R. 32 W.	11 and 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner E 3: Cedar post** Not found.  
                   Cedar 14 N77E 19 Not found. No subsequent accessories found.  
                   Y. Birch 10 S39W 40 " " " " " "

Found an old squared post which has been used locally for many years, including the location of the Plat of Fribley Subdivision.

**Corners 11 & 15:** Not established in original survey, and by approximation only, subsequently. At Corner 11, found a forester's paint line intersection, and at Corner 15, a blazed 11" spruce N58°E 2.3 ft. from true corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner E 3:** Although no original physical or subsequent record evidence was found to confirm the found post, it is generally conformable with other corners in the area, although perhaps not as exactly as one might expect it to be. Believing it undesirable to disturb local property corners in the area, I accepted it as it stands, and on 7/12/72, replaced the wood post with a monument described in C, below.

**Corner 11:** Established 8/15/72 at intersection of quarter-quarter section lines.

**Corner 15:** Established 8/14/72 on line between sec. cor. 1314.3 ft. W and 1/4 cor. 1314.4 E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.  
**Witnesses for Corner E 3:** Red Maple 5 N34°E (mag.) 23.4 ft. "S5, NBT"  
                                   W. Birch 10 N70°W (mag.) 49.4 ft. "S4, NBT"  
**Witnesses for Corner 11:** W. Spruce 7 S59°W (mag.) 99.0 ft. "1/16S, BT"  
                                   W. Spruce 9 N15°W (mag.) 140.5 ft. "1/16S, BT"  
**Witnesses for Corner 15:** W. Spruce 8 N89°W (mag.) 15.7 ft. "1/16S, BT"  
                                   W. Spruce 5 S20°W (mag.) 10.8 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE May 24, 1973  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581