

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Iron

| FOR CORNERS OF -- | LOCATED IN -- | CORNER CODE NUMBER |
|--------------------------------------|---|--------------------|
| 1. PUBLIC LAND SURVEY | T. _____ N. _____ S. _____ R. _____ E. _____ | |
| 2. PROPERTY CONTROLLING IN SECTION | 4, T. 45, N. XX R. 32 XX W. | 8a, 10, and 10a |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. _____ S. _____ R. _____ E. _____ | |
| 4. LOT NO. _____ | RECORDED PLAT _____ | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners 8a and 10 not established in original survey. At Corner 8a, found a 2" picket S4°W 3.3 ft. for an approx. line marker, and at Corner 10, found a recent 2"x2" squared spruce picket S70°E 4.6 ft. for an approx. corner.

Corner 10a: Wood post (Not found) No subsequent monuments found.

| | | |
|-------------|---------|-----|
| Tamarack 12 | N60E 25 | " " |
| Fir 6 | S42E 16 | " " |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 8a: Established 8/14/72 on E shore of lake on calculated E & W 1/4 line of Sec. 4, after first determining the size and shape of the section. W 1/4 cor. of Sec. 4 is in lake S89°49' 10"W 75.6 ft. from this corner; W 1/16 cor. on E & W 1/4 line bears N89°49' 10"E 1234.3 ft.

Corner 10: Established 8/14/72 proportionately on line between Sec. Cor. S0°36'45"W 1319.8 ft. and M.C. N0°36'45"E 1084.2 ft.

Corner 10a: Re-established 8/10/72 proportionately between Sec. Cor. N0°04'20"W 2894.9 ft. and Sec. Cor. S0°36'45"W 2404.0 ft. Bend in section line appears to conform to original field note calls to the shore of Deer Lake. Lake level is higher than in 1854 and M.C. now is in shallow water just off edge of shore. W 1/4 cor. of Sec. 4 is N0°04'20"W 235.6 ft. from this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 10: 1" I.D. x 36" iron pipe with 4" aluminum cap.

| | | | |
|------------|--------------|----------|-------------|
| W. Birch 8 | N 9°E (mag.) | 25.1 ft. | "1/16S, BT" |
| W. Birch 8 | S37°E (mag.) | 33.7 ft. | "1/16S, BT" |

Monuments for Corners 8a and 10a: 5" x 36" iron re-inforced concrete cylinder with 4" aluminum cap.

| | | | | |
|----------------------------------|-------------|---------------|----------|-------|
| Witnesses for Corner 8a: | W. Birch 8 | N68°E (mag.) | 9.7 ft. | "BT" |
| | B. Spruce 6 | S65°E (mag.) | 11.2 ft. | "BT" |
| Witnesses for Corner 10a: | Tamarack 8 | S51½°E (mag.) | 25.1 ft. | "NBT" |
| | B. Spruce 7 | N60°E (mag.) | 24.9 ft. | "NBT" |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)
 FOR STATE AND UNITED STATES AGENCIES: _____

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE May 29, 1973
 (SEAL)

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581