

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Ivan

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 45 ^{N.} xxx R. 32 ^{xx} W.	F1 & G1	
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner F1: Tamarack post (not found)
 Tamarack 14 N28E 33 " "
 White Pine 10 N51¹W 78 " "
Found a squared wood post S44⁰12¹W 36.9 ft., believed to be an approximate corner placed by Northern Paper Mills timber cruisers.

Corner G1: Ironwood post (not found)
 Sugar 14 N39E 51 " "
 Sugar 24 N14W 48 " "
Found a squared wood post N8⁰42¹W 24.2 ft., believed to be an approximate corner placed by Northern Paper Mills timber cruisers.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F1: Original field notes call for a "Stream 4 c South, south end natural meadow" 30 links west of 1/4 post. Corner as placed by undersigned on 8/2/72 by proportionate measurement on line between section corners 39.997 ch. W and 119.992 ch. E falls 27 links E of such a stream. Found post is on W side of stream; therefore, the corner as placed herein is considered better supported by the evidence on the ground.

Corner G1: Re-established 7/31/72 on line between section corners 79.995 ch. to E & W, with a true bearing by solar observation of S89⁰59¹E between them. It appears that the found post was placed at the supposed record distance from another post found by measurement to be 40.026 ch. W of it, described in "A" above, which the evidence shows is not in agreement with the original field notes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner F1: Tamarack 8 S79⁰W (mag.) 105.7 ft. "1/4S, NBT"
W. Spruce 5 S88⁰E (mag.) 84.1 ft. "1/4S, NBT"

Witnesses for Corner G1: Red Maple 10 N 9⁰W (mag.) 19.2 ft. "S33, NBT"
Sugar Maple 6 S81⁰W (mag.) 22.9 ft. "S4, NBT"
Sugar Maple 4 S34⁰E (mag.) 5.2 ft. "S3, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson CHIEF OF SURVEY PART. DATE June 12, 1973

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE June 12, 1973 (SEAL)

Arthur O. Enger
Michigan Department of Natural Resources
13581