

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Iran

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 32 XX W.	G2, G3, & H1
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|------------------------------|------------|----------------------------------|
| Corner G2: Sugar post | Not found. | No subsequent monuments found. |
| Sugar 16 N60E 13 | " " " " | " " " " |
| Y. Birch 20 S40W 11 | " " " " | " " " " |
| Corner G3: Sugar post | Not found. | Found old wood post in position. |
| Sugar 16 S62W 27 | Not found. | No subsequent accessories found. |
| Birch 16 N45E 25 | " " " " | " " " " |
| Corner H1: Fir post | " " " " | No subsequent monuments found. |
| Y. Birch 16 N49E 46 | " " " " | accessories " " |
| Sugar 16 N43W 27 | " " " " | " " " " |

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G2:** Re-established 8/1/72 proportionately on line between sec. cor. 2643.5 ft. S and sec. cor. 2641.6 ft. N.
- Corner G3:** As the found wood post checked closely with original distances to an original 1/4 corner 2641.5 ft. W and a re-established sec. cor. 5285.1 ft. N, it was accepted as duly supported by measurement evidence and re-monumented on 8/1/72.
- Corner H1:** Re-established 7/31/72 proportionately on line between sec. cor. 2639.8 ft. E and sec. cor. 7919.5 ft. W.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses for Corner G2:** Red Maple 8 N23°E (mag.) 28.0 ft. "1/4S, NBT"
Red Maple 5 N55°W (mag.) 13.9 ft. "1/4S, NBT"
- Witnesses for Corner G3:** Red Maple 18 S70°W (mag.) 4.3 ft. "S 9, NBT"
Sugar Maple 6 S67°E (mag.) 21.0 ft. "S10, NBT"
- Witnesses for Corner H1:** Sugar Maple 6 N74°W (mag.) 9.9 ft. "1/4S, NBT"
Sugar Maple 5 S 3°W (mag.) 25.5 ft. "1/4S, NBT"
Sugar Maple 4 N66°E (mag.) 22.2 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl Johnson DATE June 12, 1973

APPROVED AND SIGNED BY Arthur O. Enger DATE June 12, 1973

Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

13581