

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

14011

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 32 XX W.	B1
2. PROPERTY CONTROLLING IN SECTION 4	T. 45 N. R. 32 XX W.	3a
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B1: Fir post	Not found.	4" cedar post S83°E 7.9 ft. from corner.
Spruce 16 N42E 26	" "	No subsequent accessories found.
Maple 14 N58W 13	" "	" " " "
Corner 3a: Wood post	" "	" "
Spruce 10 N30E 27	" "	" "
Spruce 4 S50E 17	" "	" "

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B1: Because the measured distance between original section corners on this section line is only 0.8 ft. longer than the record, it was concluded that the 1/4 corner between them should be correspondingly close to the record. Therefore, on 8/2/72, re-established the corner proportionately on line between sec. corners 2640.4 ft. E and 2425.2 ft. W.

Corner 3a: Re-established 8/10/72 by proportionate measurement between sec. corners 70.179 ch. S and 10.108 ch. N, but on line between sec. cor. to N and M.C. on S side of Deer Lake, previously established. Corner falls on edge of swampy margin of lake, which may have filled in since the original survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B1: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Sugar Maple 6 N38°W (mag.)	7.2 ft. "1/4S, NBT"
Red Maple 6 S 7°W (mag.)	11.6 ft. "1/4S, NBT"

Corner 3a: 5"x 36" iron re-inforced concrete cylinder with 4" aluminum cap.

W. Pine 6 N44°E (mag.)	30.9 ft. "NBT"
B. Spruce 4 N1½°W (mag.)	13.1 ft. "NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl Johnson CHIEF OF SURVEY PARTY DATE June 12, 1973

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE June 12, 1973 (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581