

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

1/ROM

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 45 N. EX R. 32 EX W.	F 2
2. PROPERTY CONTROLLING IN SECTION 4 _____	T. 45 N. EX R. 32 EX W.	8 and 12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 14 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

None of these corners established in original survey, and apparently by approximation only, subsequently. At Corner F2, found a 3"x3" squared post S77°E 19.5 ft.; at Corner 8, found a 2"x2" stake N64°W 12.3 ft.; and at Corner 12, found a 2"x2" squared post N32°W 5.0 ft. Party or parties who set same is unknown, but as some of the controlling corners were missing or were only approximate themselves, it is difficult to see how any of these posts could be more than approximate.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner F2: Established at true intersection of quarter-section lines, after first locating or re-establishing all the 1/4 corners of Sec. 4, except the W 1/4 corner, which is in Deer Lake.

Corner 8: Established on line between calculated W 1/4 cor. and Center 1/4 cor., 1309.9 ft. from each of these corners.

Corner 12: Established on line between S 1/4 cor. 1320.2 ft. S and Center 1/4 cor. 1320.2 ft. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner F2: Balsam 8 N11°W (mag.) 18.2 ft. "1/4S, BT"
Balsam 4 S34°W (mag.) 12.6 ft. "1/4S, BT"

Witnesses for Corner 8: B. Spruce 8 S81°E (mag.) 50.9 ft. "1/16S, BT"
Balsam 5 S83°W (mag.) 23.5 ft. "1/16S, BT"

Witnesses for Corner 12: Sugar Maple 6 S57°E (mag.) 2.8 ft. "1/16S, BT"
Sugar Maple 6 N63°W (mag.) 4.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE _____ (SEAL)
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581