

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

I 1011

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|--|--------------------|
| 1. PUBLIC LAND SURVEY | T. 45 N. R. 32 E. K. W. | E1 |
| 2. PROPERTY CONTROLLING IN SECTION | T. _____ N. S. R. _____ E. W. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. S. R. _____ E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on July 24, 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--------------------|-------------|
| Sugar post | (not found) |
| Y. Birch 10 S56E 6 | (not found) |
| W. Birch 6 N35W 32 | " " |
| Fir 7 N9E 16 | " " |
| Fir 4 S66W 9 | " " |

Found a steel fence post and wood post N35°12'W 35.2 ft. as set by unknown party (possibly Northern Paper Mills personnel) for an approximate corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

In original 1849 subdivision of this township, the line between Sec. 4 & 5 was recorded as South 80.17 ch., with a W. Pine 20 line tree 1.50 ch. S of the NW corner of Sec. 4. In 1854 the work was inspected and the examining surveyor found the line to be 80.30 ch., with a W. Pine 30 line tree 1.47 ch. S of the NW cor. of Sec. 4. From a post found at SW cor. of Sec. 4, I measured to a large W. Pine stump north of Deer Lake which appeared to be approximately on the section line, finding the stump to bear N0°14'40"E 78.848 ch. from the post (bearing by solar observation). Projecting the same true line 1.47 ch. farther north, I found that point to bear N89°45'40"E 80.125 ch. and N89°59'10"W 159.990 ch. from original corners on the township line. The total distance between Sec. 4 & 5 is 80.318 ch., which corresponds to the 1854 measure of 80.30 ch. and the distances to the lake edges correspond to the original measurements also. I, therefore, placed the corner N0°14'40"E 1.47 ch. from the W. Pine stump, considering it to be duly supported by the evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Balsam 8 N54°W (mag.) 7.2 ft. "S32, NBT"
- Red Pine 6 S35½°E (mag.) 30.8 ft. "S4, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE June 12, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581