

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 32 W.	D5, C5, C11, D11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner D5: Original monument and accessories not found.
- Corner C5: Original monument and accessories not found.
- Corner C11: Original monument and accessories not found.
- Corner D11: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner D5: Restored 1-7-83 midway and on line between corners east and west.
- Corner C5: Restored 5-23-83 by land calls and corners.
- Corner C11: Restored 3-29-83 by double proportion from corners north-south-east-west. Land calls also fit good.
- Corner D11: Restored 5-5-83 midway and on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| <p><u>Corner D5:</u> Set 1" ID by 36" iron pipe near $\frac{1}{4}$ of county road.
6" Spruce S81E 19.1 ft 1/4S, NBT
5" Spruce S82W 23.6 ft 1/4S, NBT
12" Spruce N51W 24.0 ft. 1/4S, NBT</p> <p><u>Corner C5:</u> Set 1" I.D. by 30" I.P. w/4" alum. cap.
4" Balsam N56W 23.9 ft S7, NBT
5" Balsam N33E 26.4 ft. S8, NBT</p> | <p><u>Corner C11:</u> Set 1" I.D. by 32" I.P w/4" alum. cap.
3" Spruce S60E 5.0 ft S32, NBT
3" Spruce N10W 7.3 ft S30, NBT
6" Spruce S24W 23.5 ft S31, NBT</p> <p><u>Corner D11:</u> Set 1" I.D. by 32" I.P. with 4" Alum. cap.
7" Spruce S36W 27.5 ft. 1/4S, NBT
13" Spruce S46E 9.1 ft 1/4S, NBT
10" Spruce N47W 33.8 ft 1/4W, NBT</p> |
|--|--|


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 6-29-83
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006