

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

IRON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. X , R. 32 XX W.	E11
2. PROPERTY CONTROLLING IN SECTION	T. 18 45 N. XX , R. 32 XX W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E11: Original monument and accessories not found. Found old post and signature tree.
Signature tree 24" cedar S82W 8.1 ft.

Corner 2: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E11: Restored 5-4-83 at old post.

Corner 2: Established 5-23-83 midway and on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E11: Set 1" I.D. by 32" I.P. with 4" alum. cap.

5" Sugar N39E 5.2 ft S28, NBT
12" Maple S28E 21.9 ft S33, NBT
24" Cedar S82W 8.1 ft S32, NBT

Corner 2: Set 1" I.D. by 30" I.P. with 4" alum. cap.

14" Sugar S84W 11.0 ft 1/16S, BT
12" Sugar S38E 4.1 ft 1/16S, BT
4" Sugar N49E 13.7 ft 1/16S, BT


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006