

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

IRON COUNTY

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 45N X. N. R. 32 X. W.	C9, C10
2. PROPERTY CONTROLLING IN SECTION _____	30 45 N. 32 X. R. _____ W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-2-83, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C9: Original monument and accessories not found. Found 1" I.D. by unknown length iron pipe in place. Found Northern Paper Mill's location poster dated 6-10-42 in 7" dead spruce N10E 1.8 ft.

Corner C10: Original monument and accessories not found.

Corner 14: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C9: Restored at pipe. Fits good with other corners in area.

Corner C10: Restored midway and on line between corners north and south.

Corner 14: Established midway and on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C9: 1" I.D. by unknown length iron pipe.

14" W. pine N66E, 12.3 ft S20, NBT
20" W. pine N26W 18.2 ft S19, NBT
5" Maple S18W 14.5 ft S30, NBT

Corner C10: Set 1" I.D. by 32" I.P. w/4" alum. cap.

10" Spruce N28W 19.2 ft 1/4S, NBT
10" Spruce S59W 22.1 ft 1/4S, NBT
9" Balsam S07E, 26.4 1/4S, NBT

Corner 14: Set 1" I.D. by 32" I.P. w/4" alum. cap.

3" Spruce N80E 29.8 ft 1/16S, BT
4" Spruce S30E 26.1 ft 1/16S, BT
6" Tamarack S82W 38.4 ft 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 5-29-83
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

