

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

COUNTY _____

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. 32 R. 32 K. W.	A7, B7
2. PROPERTY CONTROLLING IN SECTION 18	T. 45 N. 32 R. 32 K. W.	16, 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-13-, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner A7: Original monument and accessories not found. Found old cedar post and an old cedar with axe marks N10W 2.8 ft.
- Corner B7: Original monument and accessories not found.
- Corner 16: Not set on original survey nor subsequently apparently.
- Corner 15: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner A7: Restored at old cedar post. Fits good with other corners in area.
- Corner B7: Restored by single proportion between section corners east and west.
- Corner 16: Established midway and on line between corners east and west.
- Corner 15: Established by single proportion between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| Corner A7: Set 1" I.D. by 30" I.P. w/4" alum. cap.
16" cedar S65W 12.7 ft. S24, NBT
8" maple N34E 19.7 ft. S18, NBT
4" ash S44E 17.5 ft. S19, NBT | Corner 16: Set 1" I.D. by 36" I.P. w/4" alum. cap.
16" cedar N32E 11.4 ft. 1/16S, BT
10" cedar N28W 16.0 ft. 1/16S, BT
10" cedar S34E 27.6 ft. 1/16S, BT
12" cedar squared north 4.5 ft. |
| Corner B7: Set 1" I.D. by 30" I.P. w/4" alum. cap.
25" sugar S47E 4.5 ft. 1/4S, NBT
7" sugar N41W 30.5 ft. 1/4S, NBT
24" spruce N44E 21.0 ft. 1/4S, NBT | Corner 15: Set 1" I.D. by 30" I.P. w/4" alum. cap.
24" cedar N78E 10.5 ft. 1/16S, BT
18" cedar S63E 37.0 ft. 1/16S, BT
4" maple N35W 3.5 ft. 1/16S, BT |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY DATE 11-29-83
 MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

