

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

T Iron _____ (County)	Located in:	Corner Code #/
1. Public Land Survey	T 45W R 32W	711
	T _____ R _____	G11
	T _____ R _____	G12
	T _____ R _____	
2. Property Controlling in Section	S 33 T _____ R _____	8
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on October 10, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:

F11 Original monument and accessories not found.	G11 Original monument and accessories not found. Found L.E.S. standing and in good shape. Has been used as corner since 1930.	G12 Original monument and accessories not found. Found old L.E.S. on ground.	8 Not set on original survey nor subsequently, apparently.
--	---	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F11 Restored midway and on line.	G11 Restored at L.E.S. post. Fits good with other corners in area.	G12 Restored midway and on line.	8 Established midway and on line.
--	--	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F11 Set 1" ID x 32" iron pipe w/4" aluminum cap. 4" sugar S69E 17.5' 1/4s, NBT 3" sugar N15E 9.1' 1/4s, NBT 3" sugar S85W 14.9' 1/4s, NBT	G11 Set 1" ID x 32" iron pipe w/4" aluminum cap. 10" cedar S17W 28.5' S33, NBT 6" sugar S73E 26.4' S34, NBT 4" sugar N23E 12.1' S27, NBT	G12 Set 1" ID x 32" iron pipe w/4" aluminum cap. 4" sugar S67E 11.2' 1/4s, NBT 4" sugar N19E 27.1' 1/4s, NBT 10" sugar N85W 5.2' 1/4s, NBT 2" sugar squared S62W 0.5'	8 Set 10-9-90 1" ID x 32" iron pipe w/4" aluminum cap. 12" sugar north 6.0' 1/16s, BT 9" sugar N81E 14.0' 1/16s, BT 10" sugar S38E 15.3' 1/16s, BT
--	---	---	---

Signed by Keith Sackett Date November 14, 1990

Surveyor's Michigan License No. 19006

