

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
T Iron

(County)	Located In:	Corner Code #
1. Public Land Survey	T 45W R 32W	E12
	T R	F12
	T R	
	T R	
2. Property Controlling in Section	S 33 T R	10
	S T R	12
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on October 9, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:

E12	F12	10	12
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E12	F12	10	12
Restored midway and on line.	Established at intersection of 1/4 lines	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E12	F12	10	12
Set 1" ID x 36" iron pipe w/4" aluminum cap.	Set 1" ID x 36" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.
8" sugar S85E 10.8' 1/4s, NBT	8" cedar S32E 13.5' 1/14s, BT	12" sugar N38E 13.1' 1/16s, BT	14" sugar N38E 11.6' 1/16s, BT
6" sugar N16W 2.2' 1/4s, NBT	12" cedar S32W 8.5' 1/4s, BT	18" sugar S89W 6.9' 1/16s, BT	4" sugar N54W 21.5' 1/16s, BT
4" sugar S15E 23.9' 1/4s, NBT	8" cedar N21E 18.0' 1/4s, BT	14" sugar S16E 34.9' 1/16s, BT	4" sugar S78W 37.9' 1/16s, BT

Signed by Keith Sackett Date November 14, 1990

Surveyor's Michigan License No. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
 REVISED MAY 14, 1978
 REVISED JAN. 1, 1983

