

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
2. Property Controlling in Section	S <u>31</u> T <u>45N</u> R <u>32W</u>		<u>2</u>
	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

Aug 14 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (2-Sec. 31) East 1/16 corner between Sections 30-31. 1983: Record of K.L.Sackett RLS: "Established midway and on line between corners east and west. Set 1"IDx32" I.P. w/4" alum. cap. 8" Spruce N70E 32.0', 10" Spruce S29E 40.7', 6" Spruce N08W 37.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (2-Sec. 31) Recovered the 1983 monument in good condition and at record bearing and distance from the record accessories. My measurement to this monument shows that it is located 7.46' southerly of the position of record. Removed the 1983 monument and placed a new monument midway and on a line of mean true bearing between monumented Section and Quarter corners 1314.88' east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:
 7" W.Spruce S65E 56.0' "1/16S BT"
 4" W.Spruce S61W 46.0' do
 The 1983 wits, remeasured:
 10" Spruce N89E 30.7' fd. w/ markings
 14" Spruce S22E 47.6' do
 Set squared cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 8/21/02
 Surveyor's Michigan License No. 33986

For the Michigan Dept. of Natural Resources, Office of Property Management