

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)

Located in:

Corner Code #

1. Public Land Survey	T 45N R 32W	K12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 36	T 45N R 32W
	S	T R
	S	T R
3. Miscellaneous Property in Sec.	S	T R
	S	T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

4 Apr 01 2003
 K12 Mar 26 2003

I, Stephan J. Szyzkoski, in a field survey on _____ 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	4	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(A) Description of original monument and accessories and/or subsequent re-identification: North between Sections 35&36...40.00 Set Cedar qr. post. Cedar 16 S35E 52, N.Pine 18 N69W 37. ... 80.00 Section corner. 1854: Examinations by A.B.Wood: North between Sections 25[sic] and 36...Quarter corner N.Pine 18 N51W 43, Cedar 16 S47E 40.
 (4-Sec. 36) Northwest 1/16 corner, Section 36. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) The original post was not recovered. Re-monumented the corner in the original position at record bearing and distance from the ground level remains of the 1849 bearing trees. The original record, being more consistent with the remaining evidence, was used to reestablish the corner rather than the examiner's record. Distances north and south to adjacent section corners were found to be 2624.57' and 2586.14', respectively. The southerly 1/2 mile deviates from the record substantially. Furthermore, there is a deflection at K12 of 58 minutes. These facts suggest that the random line from K7 south to K13 was not properly corrected at this corner in the original survey.
 (4-Sec. 36) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K12) Set 1"IDx32" I.pipe with 4" alum. MNR cap. Blazed, scribed, and set measuring nails in:	(4) Set 1" IDx32" I.pipe with 4" alum. MNR cap made firm in a mound of rock and portland cement concrete. Blazed, scribed, and set measuring nails in:
4" Sugar N36E 20.4'	"1/4S NBT"
4" Y.Birch S39E 10.4'	do
10" N.Spruce S25W 35.9'	do
7" Sugar S74W 30.3'	do
Set squared spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.	7" Spruce N60E 53.40' 13" Cedar S84E 48.95' 4" Balsam N80W 48.85' 7" Maple N34W 49.05' do Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyzkoski
 Surveyor's Michigan License No. 33986

Date 5/29/03

For the Michigan Department of Natural Resources - Office of Land and Facilities