

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 32W	F11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 33 T 45N R 32W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11						●							
12	31		32		33		34		35		36		
13						●							

I, Stephan J. Szyszkoski, in a field survey on F11 05/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F11) Quarter corner common to Sections 28 and 33. 1990 - Restored by K.L.Sackett RLS midway and on line between Section corners. Set 1"IDx32" iron pipe with 4" aluminum MDNR cap. 4" Sugar S69E 17.5', 3" Sugar N15E 9.1', 3" Sugar S85W 14.9'.

(13-Sec. 33) Southeast 1/16 corner, Section 33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F11) Found the 1990 monument in good condition and at record bearing and distance from two of the 1990 NBTs: The Sugars NE and SE are in good condition with overgrown blazes. Left the monument in place and marked two new witnesses as described below.

(13-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Sugar N23E 9.1' old blazes (1990 NBT)
 6" Sugar S69E 17.7' do do
 5" Sugar S43W 20.9' mrkd "1/4S NBT"
 24" Y.Birch N74W 14.55' do
 Bearings are magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" Sugar S79E 5.4' mrkd "1/16S BT"
 6" Sugar S10E 23.15' do
 8" Sugar S72W 25.45' do
 7" Sugar N38W 10.6' do
 Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 05/27/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities