

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>33</u> T <u>45N</u> R <u>32W</u>	<u>16</u>
	S <u>33</u> T <u>45N</u> R <u>32W</u>	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 12 05/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 33) East 1/16 corner between Section 33 T45N-R32W and Section 4 T44N-R32W. 1968 - A.O.Enger RLS established the corner midway and on the line between Section corner 20.01 chains east and Quarter corner 20.01 chains west. Set 1"IDx36" I.pipe with 4" aluminum cap. Sugar Maple 14" N23W 27.5 links, Sugar Maple 8" S27W 34 links.

(12-Sec. 33) South 1/16 corner, Section 33. 1990 - Established by K.L.Sackett RLS midway and on a straight line between Center of Section 33 and South 1/4 corner of Section 33. Set 1"IDx36" iron pipe with 4" aluminum cap. 14" Sugar N38E 11.6', 4" Sugar N54W 21.5', 4" Sugar S78W 37.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 33) Found the 1968 monument in good condition, substantially at the record position, and at record bearing and distance from the remaining Sugar BT 18" N16W 27.5 links [recorded as 14" dia. N23W 27.5 links], in good condition with overgrown blazes facing the monument. Accepted the monument as a careful and faithful establishment of the position of the corner.

(12-Sec. 33) Recovered the 1990 monument in good condition and at record bearing and distance from the 1990 witness trees, both in good condition. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 18" Sugar N16W 19.0' overgrown blazes 1968 BT
 7" Sugar S81E 32.9' mrkd "1/16S BT"
 5" Sugar S05W 25.85' do
 7" Sugar N50W 5.85' do
 Set sq'd cedar post adjacent. Bearings are magnetic.

(12) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar N53W 21.75' overgrown blazes 1990 BT
 16" Sugar N39E 11.95' old marks visible do
 6" Y.Birch S52E 35.3' mrkd "1/16S BT"
 9" W.Birch S49W 9.85' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/27/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities