

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 45 NR. 33 W.

Iron COUNTY

DESCRIPTION OF CORNER Meander corner between Sec.'s 35-36 on south shore of
Buck Lake

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 12" W. Pine S 84° E 8 links

"M.C. NBT"

8" Cedar S 23° W 100 links

"M.C. NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Replaced meander corner from one white pine B.T. bearing S 30° E 12 links.
B.T. is stub with all scribe marks readable and in excellent condition.

Found by pacing with hand compass from town line south.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 6/6/57