

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Iron

_____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>33W</u>	<u>H13</u>
	T <u>45N</u> R <u>33W</u>	<u>G13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

G13 February 25, 1995

I, Stephan J. Szyszkoski, in a field survey on H13 October 09, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

{H13} Quarter corner common to Section 34 T45N-R33W and Section 3 T44N-R33W. Corner established in 1845 by Austin Burt as follows:
 "West on South side of Sec. 34...36.00 A ledge of Greenstone Rock 20 ft. high facing the North C. E&W, 40.00 Set Maple Post Gr. Sec. Cor. Cedar 12 N33E 5, Y. Birch 10 N36W 24;...59.00 Enter Swamp C. NSW...76.00 Leave Swamp C MNW.

{G13} Corner common to Sections 33-34 T45N-R33W and Sections 3-4 T44N-R33W. Corner restored in 1984 by Keith Sackett, RLS who placed a 1" I.D.x32" iron pipe with 4" aluminum MDNR cap. No witnesses noted on the 1984 LCRC.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

{H13} Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on a straight line between adjacent section corners 2637.11 feet east and west. At this position the swamp and ledge calls noted above check well with the record. The two stream calls which fall in between the swamp edges at 59.00 and 76.00 chains are now obliterated as they fall in a large beaver flooding. At the position for the corner, I placed a 1" I.D.x32" iron pipe capped with a yellow plastic cap stamped "MICH DNR LS 33986".

{G13} Found and accepted a 1" I.D.iron pipe with 4" aluminum MDNR tablet, appropriately stamped. Distance east to "Compact Greenstone" noted in the original record checks but the call is not very distinct. Distances east and west to recorded corners check well with the record. Left the monument in place and marked four witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

{H13} Set 1" pipe with plastic cap.
 Blazed and scribed the following bearing trees:

12" Spruce N76E 24.8' "1/4S NBT"
 5" Balsam S43E 9.9' "1/4S NBT"
 12" Maple S15W 38.6' "1/4S NBT"
 9" Balsam N53W 34.9' "1/4S NBT"

Face of large rock N45E 3.5'
 Placed a 4" Cedar post adjacent
 Bearings are magnetic.

{G13} Found 1" pipe with MDNR cap
 Blazed and scribed the following new bearing trees:

5" Spruce S20W 29.8' "S4 NBT"
 6" Spruce N89W 12.4' "S33 NBT"
 6" Balsam S06W 27.2' "S4 NBT"
 10" Aspen N76E 28.8' "S34 NBT"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski

Date 10-19-95

Surveyor's Michigan License No. 33986