

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
 Iron \_\_\_\_\_

	Located In:	Corner Code #
	44-33	
1. Public Land Survey	T 45N R33W	J13
	T 45N R33W	K13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 35 T 45N R33W	16
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on February 23, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(J13) Quarter corner common to Section 35 T45N-R33W and Section 2 T44N-R33W. Corner reestablished by proportionate measurement in 1964 by Neal Spherhake, RLS: Galvanized iron pipe, 3 ft. long, 1" dia. with aluminum cap. Spruce 8 S73E 30 links, Cherry 9 N23E 62 links. Spherhake notes distance east and west to adjacent section corners to be 39.935 chains.  
 (K13) Corner common to Sections 35-36 T45N-R33W, and Sections 1-2 T44N-R33W. Corner re-monumented in 1957 by Billy O. Buckler RLS from the remains of an original bearing tree: Monument is 1" pipe with 4" brass cap witnessed by 8" Red Pine S44W 92 links, 14" R. Pine S12E 107 links, 7" Soft Maple N82E 4.5 links.  
 (16-Sec. 35) East 1/16 corner between Section 35 T45N-R33W and Section 2 T44N-R33W. Corner not established in the original survey. Established by Neal Spherhake for Kimberly-Clark Corp. ca. 1964.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


(J13) Found the 1964 monument in good condition, at record bearing and distance from the Spruce N8T, now 20" dia. with healed blazes. The Cherry was not recovered. Left the monument in place and marked three new bearing trees as described below. Found the distance east to Section corner to be 39.8945 chains.  
 (K13) Found and accepted the 1957 monument in good condition and at substantially record bearing and distance from the 3 1957 witnesses: The 14" Red Pine was observed to be S05E. Both pines are in good condition with healed blazes. The Soft Maple is dead and down - only a stump remaining. Left the monument in place and marked 2 new bearing trees as described below.  
 (16-Sec. 35) Found a Kimberly-Clark Monument: A 1" I.D. iron pipe capped with a 4" aluminum cap, stamped with appropriate markings and "Spherhake RLS 7876". I found the monument to be 0.75' South of a straight line between adjacent corners, and 0.44' East of the midpoint. I accepted the monument as a careful and faithful determination of the position of the corner. Left the monument in place and marked witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J13) Found 1" pipe with 4" aluminum Kimberly Clark cap. Blazed and scribed the following new bearing trees: 2" Spruce N23W 30.7' "1/4S NBT" 6" Balsam S76W 27.4' "1/4S NBT" 13" Balsam S27W 22.4' "1/4S NBT" The 1964 NBT: Spruce 20" S65E 19.0' Bearings are magnetic.	(K13) Found 1" iron pipe with 4" brass MI Dept. of Conservation cap. Blazed and scribed the following: 14" Cedar N60E 64.3' "S36 NBT" 12" R. Pine N52W 49.5' (slope) "S35 NBT" Bearings are magnetic.	(16) Found a 1" iron pipe with a 4" Kimberly-Clark cap. Blazed and scribed the following bearing trees: 5" Balsam N48E 20.0' "1/16S BT" 6" Balsam N17W 29.7' "1/16S BT" 6" Spruce S60W 13.8' "1/16S BT" 7" Maple S16W 21.7' "1/16S BT" Bearings are magnetic.
---	--	--

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986



Date 3-1-95