

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> ^{N.} XX , R. <u>34</u> ^{XX} W.	D9
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	, T. <u>45</u> ^{N.} XX , R. <u>34</u> ^{XX} W.	1 & 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S., R. _____ ^{E.} W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D 9: Wood post (Not found. No subsequent monuments found)
 W. Birch 10 N10E 25 " " No subsequent accessories found)
 W. Birch 12 S23W 39 " " " " " "

Corners 1 & 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner D9:** Re-established 8/20/73 on line between Sec. Corners 42.471 ch. W and 36.208 ch. E. Measurements and comparison of distances actually found with distances recorded in original field notes to a stream crossing, indicate the probability of a mistake in the original survey (possibly more than one). Previous experience in this twp. indicates that mention of natural objects encountered is a more reliable indicator of where the original corners were placed (with certain exceptions) than are the reported measurements; therefore this line has uneven lengths between sec. corners and 1/4 corner.
- Corner 1:** Established 8/21/73 on line between Sec. Cor. 19.986 ch. W and 1/4 cor. 22.485 ch. E; this is believed to place the mistake mentioned above in the place where it was originally made.
- Corner 2:** Established 8/21/73 on line between 1/4 cor. 18.104 ch. W and Sec. Cor. 18.104 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner D9:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Cedar 14 N67°E (mag.) 23.6 ft. "1/4S, NBT"
 W. Spruce 10 N84½°W (mag.) 38.2 ft. "1/4S, NBT"
 Also squared & scribed a 7" balsam N61°W 2.0 ft. from corner.
- Corner 1:** 1" I.D. x 40" iron pipe with 3½" aluminum cap.
 Cedar 10 N82½°E (mag.) 16.5 ft. "1/16S, BT"
 Y. Birch 10 N15°W (mag.) 19.5 ft. "1/16S, BT"
- Corner 2:** 1" I.D. x 38" iron pipe with 3½" aluminum cap.
 W. Spruce 8 S 9½°W (mag.) 10.8 ft. "1/16S, BT"
 W. Spruce 8 S42½°E (mag.) 9.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE April 19, 1974

MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

