

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> <sup>N.</sup> <del>XX</del> <sub>W.</sub> , R. <u>34</u> <sup>XX</sup>	C8 & C9
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ <sup>N.</sup> <sub>S.</sub> , R. _____ <sup>E.</sup> <sub>W.</sub>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <sub>S.</sub> , R. _____ <sup>E.</sup> <sub>W.</sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

<b>Corner C8: Wood post</b>	(Not found. No subsequent monuments found.)
Spruce 6 N15E 52	(Not found. No subsequent accessories found.)
Tamarack 10 S10W 39	(Not found. No subsequent accessories found.)
<b>Corner C9: Wood post</b>	(Not found. No subsequent monuments found.)
Tamarack 10 S44W 30	(Not found. No subsequent accessories found.)
Tamarack 8 N56E 36	(Not found. No subsequent accessories found.)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner C8:** Re-established 1/18/74 on line between Section Corners 40.024 ch. to N and to S. Corner falls in beaver meadow.

**Corner C9:** Re-established 9/8/72 proportionately between Section Corners 1 mi. N and 2 mi. S, and at the record distance from the section corner on the township line to the W. This position achieves the best conformity with calls to natural objects mentioned in the original field notes. Found a stream 5 lks. wide, course SE, 1.95 ch. N of corner and the same stream 7 lks. wide, course SE, 2.58 ch. E of corner, the record distances being 2.00 ch. and 2.60 ch., respectively.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner C8:** 1" I.D. x 36" iron pipe with 4" aluminum cap.  
 Tamarack 12 S29½°W (mag.) 142.9 ft. "1/4S, NBT"  
 Tamarack 11 N29°W (mag.) 162.4 ft. "1/4S, NBT"

**Corner C9:** 1" I.D. x 36" iron pipe with 3½" aluminum cap  
 B. Spruce 5 N68°E (mag.) 26.5 ft. "S20, NBT"  
 B. Spruce 5 N74½°W (mag.) 10.2 ft. "S19, NBT"  
 B. Spruce 6 S48½°E (mag.) 5.8 ft. "S29, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE April 17, 1974  
MICHIGAN REGISTERED LAND SURVEYOR

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

