

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 45 <sup>N.</sup> <del>S.</del> R. 34 <sup>W.</sup> <del>E.</del>	F5
2. PROPERTY CONTROLLING IN SECTION _____	9, T. 45N <sup>N.</sup> <del>S.</del> R. 34 <sup>W.</sup> <del>E.</del>	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>S.</del> R. _____ <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner F5: Wood post (Not found. See below for subsequent monument.)
- Cedar 12 N80E 21 (Not found. No subsequent accessories found.)
- Fir 6 S88W 10 (Not found. No subsequent accessories found.)

Corner 15: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner F5: Re-established 8/15/74 on line between Sec. Cor. 40.173 ch. E and Sec. Cor. 39.456 ch. W. This corner had been re-established on 11/10/72 by the undersigned at a slightly different place, but new information having come to light about the location of Sec. Cor. 9, 10, 15 & 16 subsequent to its first re-establishment, this corner was moved to conform. Found a 4"x4"x6" squared wood post N31°E 1.70 ch. for an approx. corner.

Corner 15: Re-established 8/19/74 on line between 1/4 cor. 19.404 ch. E and Sec. Cor. 20.052 ch. W. Because of error in original record measurement, believed caused by deputy surveyor's estimate, rather than actual measurement, of distance across Porter

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Creek, uneven distances were used by undersigned, in order to place error where it most likely was made. Changed by undersigned from initial establishment on 11/17/72. (See Corner F5 for reason.)
- Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses for Corner F5: Sugar Maple 10 N16°E (mag.) 27.4 ft. "1/4S, NBT"
  - Sugar Maple 8 N44°W (mag.) 19.4 ft. "1/4S, NBT"
  - Red Maple 8 S34°W (mag.) 20.7 ft. "1/4S, NBT"
  - Witnesses for Corner 15: B. Spruce 5 N24°E (mag.) 13.8 ft. "1/16S, BT"
  - B. Spruce 6 S52°E (mag.) 38.0 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE June 23, 1975

Arthur O. Enger  
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

