

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> ^{N.} XXX R. <u>34</u> ^{XXX} W.	E4 and F5
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>45</u> ^{N.} XXX R. <u>34</u> ^{XXX} W.	3 & 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E4: Wood post Not found. No subsequent monuments found.
 Sugar 10 N35E 28) Not found. No subsequent accessories found.
 Sugar 10 S35E 34)

Corner F5: Wood post Not found. Found wood post N33°E 164 lks.
 Fir 6 S88W 10) Not found. No subsequent monuments found.
 Cedar 12 N80E 21)

Corners 3 and 15: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E4: Re-established 11/27/72 on line between section corners 39.961 ch. to N and to S.
Corner F5: Re-established 11/10/72 on line between section corners 40.114 ch. E and 39.433 ch. W. Distances unequal because of belief that record distance across Porter Creek is incorrect--probably estimated rather than measured. Record distance is 230 links, actual distance is 166 links, with no possibility of river having been wider 125 years ago. Wood post set by unknown parties, for an approx. corner.
Corner 3: Established 11/27/72 on line between 1/4 corner 19.981 ch. S and Sec. Corner 19.981 ch. N. **Corner 15:** Established 11/17/72 on line between Sec. Cor. 20.000 ch. W and 1/4 cor. 19.433 ch. E. Error noted for Corner F5 was all put in the E half of this line segment, where it probably occurred.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all four corners: 1" I.D. by 36" iron pipe with 4" aluminum cap.

Witnesses for Corner E4: Sugar Maple 11 S87°E (mag.) 10.1 ft. "1/4S, NBT"
 Sugar Maple 11 S62°W (mag.) 20.5 ft. "1/4S, NBT"
 Sugar Maple 14 N37°W (mag.) 21.0 ft. "1/4S, NBT"

Witnesses for Corner F5: Red Maple 8 S22°W (mag.) 24.8 ft. "1/4S, NBT"
 Sugar Maple 10 N27°E (mag.) 23.4 ft. "1/4S, NBT"
 Sugar Maple 8 N52½°W (mag.) 14.5 ft. "1/4S, NBT"

Witnesses for Corner 3: Cedar 16 N83°W (mag.) 7.1 ft. "1/16S, BT"
 Cedar 16 S21½°E (mag.) 10.4 ft. "1/16S, BT"

Witnesses for Corner 15: B. Spruce 5 N43°E (mag.) 13.8 ft. "1/16S, BT"
 B. Spruce 6 S54°E (mag.) 42.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 28, 1973
MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

