

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> ^{N.} S. R. <u>34</u> ^{E.} W.	<u>G4</u>
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>45</u> ^{N.} S. R. <u>34</u> ^{E.} W.	<u>10 & 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G4: Wood Post (Not found. Found mound of rocks in place.)
 Sugar 10 S40E 20 (Found)
 Cedar 8 N60W 09 (Found)

Corners 10 & 15: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G4: Re-monumented as shown in C, below, on 8/5/74. Cedar BT is a 12' high stub, 18" dia.; found face with scribe marks "BT" about 5" inside tree, grown completely over. Many external blazes and cruiser's names on stub. Maple BT, still alive, but hollow; identified by relative position.
 Corner 10: Established 8/9/74 on line between Sec. Cor. 19.504 ch. S and 1/4 cor. 19.504 ch. N.
 Corner 15: Established 8/5/74 on line between Sec. Cor. 20.252 ch. W and West M.C. 2.514 ch. E, which agrees closely with original field note distance bet. Sec. Cor. and river bank.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument for all three corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

Witnesses for Corner G4: Cedar 15 N31°W (mag.) 24.2 ft. "1/4S, NBT"
 Hemlock 16 N41°E (mag.) 51.1 ft. "1/4S, NBT"

Witnesses for Corner 10: Sugar Maple 9 S62°E (mag.) 5.3 ft. "1/16S, BT"
 Sugar Maple 13 N49°W (mag.) 19.2 ft. "1/16S, BT"

Witnesses for Corner 15: Cedar 14 S84°W (mag.) 17.7 ft. "1/16S, BT"
 Cedar 16 S72°E (mag.) 31.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE June 23
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

