

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. 45 S. N. R. 34 W. E. | H5 |
| 2. PROPERTY CONTROLLING IN SECTION _____ | T. 45 S. N. R. 34 W. E. | 15a & 15b |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S. R. _____ E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner H5: No evidence of original post or its accessories found. Found a 1" x 38" square iron drill rod in place, origin unknown.

Corners 15a & 15b: These are meanders on Net River between Sec. 10 & 15. No evidence of original posts or their accessories found. No subsequent monuments found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner H5: Accepted monument as found, as its alinement is consistent with section corners to E and to W. Placed a new monument described in C, below, on 9/11/73.

Corner 15a: Re-established 9/11/73 on East bank of Net River on line between Sec. Cor. 27.668 ch. W and 1/4 cor. 14.031 ch. E.

Corner 15b: Re-established 8/5/74 on West bank of Net River on line between Sec. Cor. 22.766 ch. W and 1/4 cor. 18.847 ch. E.

Note: M.C.'s not placed proportionately, but set in-shore to protect them from spring-time high water. West M.C. bears N88°49.5'W 4.888 ch. from East M.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H5: 1" I.D. x 39" iron pipe with 3 1/2" aluminum cap.
 Sugar Maple 14 S64°W (mag.) 17.9 ft. "1/4S, NBT"
 Red Maple 7 S50°E (mag.) 35.9 ft. "1/4S, NBT"

Also squared and scribed an 8" sugar maple S67°W 2.0 feet.
Monuments for Corners 15a & 15b: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

Witnesses for Corner 15a: B. Ash 8 S34°E (mag.) 17.8 ft. "M.C., NBT"
 W. Birch 10 N52°E (mag.) 44.6 ft. "M.C., NBT"

Witnesses for Corner 15b: Cedar 6 S50°W (mag.) 19.3 ft. "M.C., NBT"
 Cedar 12 N16°W (mag.) 29.8 ft. "M.C., NBT"

Also squared and scribed a crooked 6" cedar N16°W 11.6 ft., measured from ground level on tree.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE June 29, 1975
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

